

SCHEDULE - B


Name of the Work: Construction of Cement concrete to Basaveshwara Layout Cross roads in Ward No.18


Sl. No	Description of item	Quantity	Unit	Rate (Rs)	
				In figures	In words
1	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T & P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metrs complete as per specifications. i) Lime / Cement Concrete I. By Manual Means A Lime Concrete, cement concrete grade M-10 and below. MORTH Specification No.202 Page No.147 I No.18.17	315.00	Cum	316.44	Rupees Three Hundred Sixteen And Paise Forty Four Only
2	Providing, laying, spreading and compacting stone aggregates of specific sizes to water bound macadam specifications including spreading in uniform thickness, hand packing, rolling with 3-wheeled steel/vibratory roller 8-10 tonnes in stages to proper grade and camber, applying and brooming requisite type of screening/binding materials to fill up the interstices of coarse aggregates, watering and compacting to the required density complete as per Specification. A by Mannual means MORTH Specification No.404 (Type B 11.2mm for grading III) P.165-I.20.14 (14.3)	180.00	Cum	1867.32	Rupees One Thousand Eight Hundred Sixty Seven And Paise Thirty Two Only
3	Cement Concrete Pavement - Construction of un-reinforced, dowel jointed, plain cement concrete pavement over a prepared sub base with OPC cement design mix M30 at 360 Kg per cum, with 25mm and down size graded granite metal coarse aggregate at 0.69 cum and fine aggregates @ 0.46 cum with superplastizezer at 3lts conforming to IS 9103-1999 reaffirmed 2008, coarse and fine aggregate conforming to IS.383, mixed in a batching and mixing plant as per approved mix design, transported to site, laid with a fixed form or slip form paver, spread, compacted and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints, joint filler, separation membrane, sealant primer, joint sealant, debonding strip, dowel bar, tie rod, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications MORTH Specification No.602 P.185-I.22.2	135.00	Cum	6943.32	Rupees Six Thousand Nine Hundred Forty Three And Paise Thirty Two Only

Executive Engineer-2,
KRIDL, BBMP, Bangalore

Executive Engineer (Hebbal)

4	Vacuum de-watering with vacuum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc. with all lead and lift P No 190, I No 22.7	900.00	Sqm	97.20	Rupees Ninety Seven And Paise Twenty Only
5	Providing groove cutting for width of 5mm to 10 mm and depth 80mm-100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade, coolant etc. including cleaning of groove & providing sand and hot bitumen fillers and filler metal etc. including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. P No 191, I No 22.8	65.00	Rmt	124.20	Rupees One Hundred Twenty Four And Paise Twenty Only
6	Providing TMT Steel reinforcement for RCC work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 P 19-1.4.46	5.00	Tonn	69805.80	Rupees Sixty Nine Thousand Eight Hundred Five And Paise Eighty Only
7	Disposing of debris to the final place of disposal with all lead and lift and as directed by the engineer in charge of the work	180.00	Cum	94.82	Rupees Ninety Four And Paise Eighty Two Only


 Executive Engineer-2,
 KRIDL, BBMP, Bangalore
 Contractor


 Executive Engineer (Hebbal)